SPORTSRADIO 610 WIP

Spectacor Broadcasting
441 N. 5th Street, Philadelphia, PA 19123-4089 • (215) 922-5000 • Fax (215) 922-2434

April 19, 1990

Bill Burrows
709 Division St.
Gloucester City, NJ 08030-2337

This letter will confirm reception of 610 WIP All Sportsradio on December 4, 1989 (date) at 1:57PM (time) EST.

Station WIP (AM), Philadelphia operates on an assigned frequency of 610 kHz., 5000 Watts day and night with a directional antenna system consisting of two tapered, self-supporting, series excited, vertical radiators top loaded with a 30 foot tophat, with an overall height of 280 feet spaced 810 feet (181 degrees).

The ground system consists of 120 equally spaced, buried copper radials varying in length from 200 to 400 feet, plus a 40x40 foot ground screen about the base of each tower.

Transmitters are Bauer, FB-5V, using a 4CX5000A final RF amplifiers, located in Bellmawr, New Jersey.

Thanks for listening to 610 WIP All Sportsradio.

Regards,

William J. Rinier
Chief Engineer

:csa